Sl No	Description of Work	Unit	Sanctioned Quantity	Rates to be Quoted by Contractor	
				In Figures	In Words
1	~~KSRB 4.2.7~~ : Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm cum and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, Unties, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fiHets Etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications, ~~specification No. KBS 4.t, 4.6~~	Cum	56.57		
2	~~KSRB 4.2.10~~ : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.05175cum and fine aggregtes @ 0.0345cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete but excluding cost of reinforcement as per specifications. ~~Specification No. KBS 4.1, 4.6~~	Sqm	6.72		
3	~~KSRB 4.1.6~~ ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded cum granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, nciuding cost of all materials, labour, HOM of machinery, curing complete as per specifications. ~~Specification No. KBS 4.1, 4.2~~	Cum	0.22		

NO's of Correction - Six (06)

4	~~KSRB 4-6.5~~ : Providing and removing centering, shuttering, strutting, propping etc., for Sqm. columns, pillars, post and struts, square / rectangular/ polygon in plan including cost of all materials, labour complete as per specifications. ~~Specification No. KBS 4.6.2~~	Sqm	148.78		
5	~~KSRB 4-6.2~~ : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaitons.up to 3.50m from Ground level. ~~Specification No. KBS 4.6.2~~	Sqm	179.00		
6	~~KSRB 4-6.9~~ Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications. ~~Specification No. KBS 4.6.2~~	Sqm	19.36		
7	~~KSRB 4-6.7~~ :Providing and removing centering, shuttering, strutting, Sqm propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications. ~~Specification No. KBS 4.6.2~~	Sqm	191.92		
8	~~KSRB 4-6.10~~ Providing and removing centering, shuttering, strutting, Sqm propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specifications. ~~Specification No. KBS 4.6.2~~	Sqm	9.84		
9	~~KSRB 4.9.2~~ : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. ~~Specification No. KBS 4.6.3 TMT bars Fe 500~~	MTs	6.06		

NO'S of Correction - TWelWe(12)

CONTRACTOR

EXECUTIVE ENGINEER

10	~~KSRB 6-5.2~~ : Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 5.0Newton per sqmm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. ~~Specification No. KBS 6.2~~	Cum	49.03		
11	~~KSRB 9.4-2~~ : Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications. ~~Specification No. KBS 9.33~~	Cum	0.40		
12	~~KSRB 9-27.1~~ : Fixing of door frame in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications.	Nos	4.00		
13	~~KSRB 9-13-1~~: Providing and fixing in position shutters for doors made out of Honne wood styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 18mm thick of exterior grade Melamine impregnated prelamination particle board of approved colour on both sides including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) ~~Specification No. KBS 9.34, 9.26.4~~	Sqm	8.40		

No's of correction - seven (7)

14	~~KSRB 7.10~~ : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame section of size 61.85x31.75mm. with 1.2mm thick, bottom section weight 0.695 kg/m, sides and top sections 1.3 mm. thick weight 0.659 kg/m; and shutter comprising top and bottom section of size 40mmx18mm, 1.25mm thick 0.417 kg./m; shutter outer side 40mmx18mm, 1.25mm.thick weight 0.417 kg/m, shutter interlock section 40mmx26.7mm, 1.1mm thick, weight 0.469 kg/m. the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; and providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted in the assembled frame stiffened with end clips at corners angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be with necessary steel screws, raui plugs, or teak wood gatties including cutting masonry or concrete and making good the originai surface using cement mortar, aluminium sections pretreated for removal of any Specification No. KBS using aluminium section powdered coated to a minimum of 60-70 microns with exterior durable pure polyester grade powder of approved quality.	Sqm	26.88		
15	~~KSRB 7.9~~ : Providing and fixing M.S.grill work for windows and Kgs ventilators using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. ~~Specification No. KBS 7.12~~	KGs	564.48		

NO'S of Correction - Three(03)

CONTRACTOR

EXECUTIVE ENGINEER

16	Providing and fixing M.S. Grill over existing compound wall as per using 16mm x 16mm M.S. Square rod at 150mm c/c spacing and 6mm x 40mm M.S. flats at horizontal and 6mm x12mm M.S. flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding wherever necessary. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per specification	Sqm	30.00		
17	~~KSRB 15-3.10~~ : Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, including providing and removing scaffolding, cost of materials, labour, curing etc., complete as per specification.	Sqm	537.46		
18	~~KSRB15-3.7~~ : Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specification	Sqm	265.92		
19	~~KSRB 15-3-13~~ : Providing 12mm thick cement piaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, including providing and removing scaffolding, cost of materials, labour, curing etc., complete as per specification.	Sqm	249.84		
20	~~KSRB15-7~~ : Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications.	Sqm	515.76		

NO'S of Correction - Four(04)

CONTRACTOR

EXECUTIVE ENGINEER

21	Providing and laying flooring using prepolished, water cut/gang saw using 10mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to mach shade of granite slabs including laying POP on finished surface and cleaning the surface, including the cost of all materials, mortar and labours etc., complete as per specificationsusing silver grey granite / Multy Red / Ruby Red I Black / Hassan Green Granite of width not less than 1200mm	Sqm	188.45		
22	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of all materials, cost of labour and scaffolding etc., complete as per the specification. Area to be considered - (a) 100% for fresh surface (b) Upto 10 % for repainting	Sqm	515.76		
23	~~KSRB 15-15.1~~ : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.	Sqm	515.76		
24	~~KSRB 15-15.2~~ : Extra over Item 15-15.1 for painting two coats with plastic emulsion paint of approved brand and shade on ceiling and / or sloping roof as per specifications.	Sqm	515.76		

No's of Correction - TWO(02)

25	Providing textured paint of approved quality, colour and shade to wall surface after cleaning and rubbing the wall surface with wire brush of medium size emery stone to remove all the loosely adhering particles, the surface is then cleaned with water and ensured that it is in line and level. The textured material is then mixed with 40-50% of clean water until a homogeneous thick slurry is formed, the slurry is left for 5-10 min, to react completely with ingredients. The textured finish prepared as above is then applied to the wall surface with suitable roller/spray gun/putty/ blade/ trowel to get the desired finish. The finished surface shall be applied with two coats of exterior paint of approved shade. The rate includes providing and removing scaffolding, all lead and lift and all other incidental charges	Sqm	537.46		
26	~~KSRB 15-17.5~~: Applying priming coat over new wood surface and / or wood based surface after preparing the surface after throughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, complete as per specifications	Sqm	21.60		
27	~~KSRB 15-17.6~~: Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials,labour, complete as per specifications.	Sqm	21.60		
28	~~KSRB 15-17.8~~ : Extra over Item No. 15-17.6 for applying every subsequent coat of enamel paint to give an even shade after cleaning the surface of all dirt, dust and foreign matter, sand papering includingcost of materials, labour, complete as per specifications.	Sqm	21.60		
29	~~KSRB 15-18.1~~ : Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications.	Sqm	134.76		

No's of Correction - Four (04)

30	~~KSRB 15-18.2~~ : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	Sqm	134.76		
31	~~KSRB 15.8.1~~ Providing and fixing plaster mesh 150mm wide manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along route of walls chipped for services, junction between RCC and brick walls including cost of materials, labour for fixing complete as per specifications, (length of mesh only be measured for payment)	M	152.40		
32	0179 Handles to full width 2m long	Each	6.00		
	0188 Hinges 5" heavy duty		9.00		
	Providing Screws		60.00		
	0220 Locking arrangements		4.00		
33	~~KSRB 8.6-8~~ : Providing and fixing on wall surface 4.0 kg / sq.cm H.D.P.E. rain down water pipes 110 mm outer dia. approved make and brand with necessary specials like shoes, bends and offsets fixed with iron clamps, wall plugs, screws, including cost of materials, labour, complete as per specifications.	M	24.00		

No's of Correction - Three (03)

CONTRACTOR

EXECUTIVE ENGINEER

34	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 19/20mm dia 2mm thick conforming to IS 2509 with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipes ends should be covred using PVC end enclosures. run with 18SWG GI fish wire wherever necessary.19/20mm dia 2mm thick	Rmt	50.00		
35	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 25mm dia 2mm thick conforming to IS 2509 with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipes ends should be covred using PVC end enclosures. run with 18SWG GI fish wire wherever necessary.a)25mm dia 2 mm thick	Rmt	50.00		
36	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 19/20mm dia 2mm metal/PVC junction boxes adhesive paste etc. By groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary.19/20mm dia 2mm thick	Rmt	50.00		
37	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 25mm dia 2.mm metal/PVC junction boxes adhesive paste etc. By groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary.a)25mm dia 2 mm thick	Rmt	50.00		
38	Concealed Conduit System Supplying heavy gauge PVC conduit pipe 32mm dia 2.5mm metal/PVC junction boxes adhesive paste etc. By groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary.32mm dia 2.5 mm thick	Rmt	30.00		

No's of Correction - 0

39	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multistrand Copper conductor single core cable in open or concealed system of wiring with specified IS-694:1990 & conforming to GTP of	Rmt	0.00		
	Group-A.		0.00		
	1.0 Sqm		150.00		
	1.5Sqm		150.00		
	2.5Sqm		100.00		
	4.0Sqm		100.00		
	10.0Sqm		20.00		
40	Point wiring using Copper wire without switch.Supplying and wiring adopting loop system in existing PVC Conduit/casing capping using 1100V Grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2x1.5 Sq.mm Cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose lenght in a wood/PVC round block. complete for each outlet.(5/2.3	Each Point	0.00		
	Using class A materials		0.00		
	Short point up to 3mtrs from tapping point to out let via switch		10.00		
	Medium point a above 3mtr up to 6mtr from tapping point to out let via switch		10.00		

NO'S of Correction-0

	Long point a above 6mtr up to 10mtr from tapping point to out let via switch		8.00		
41	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve , indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required conforming to IEC60898.5-32Amps DP		0.00		
	5-32Amps DP MCB (,I No-6.15.5 of PWD S.R 2014-15)	No	2.00		
	5-32Amps SP MCB (,I No-6.15.1 of PWD S.R 2014-15)		2.00		
42	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure,III-Single Door.Group A12Way SP &N	No	1.00		
43	Supply and fixing of bakelite D.P/Socket/ switch with/without neon indicator over existing wood board or flush mounting in plastic plates/nitches as per IS 1293 and IS 3854 Group-A.32Amps Flush/projected types DP switch	No	8.00		
44	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plateas per IS 3854 and IS 1293 Group "A" materials k) TV/Telephone socket (8/18)	No	20.00		

No's of Correction - 0

45	Supply patti type fluorescent tube light fitting of 4'-28 watts fluorescent tube fitting, made out of M.S sheet and stove enameled with HF Electronic Ballast,locking type brass contact holders mounted on double fold type sheet base fully wired for use on 230 Volts A C Supply including T5 lamp Group - A	No	20.00		
46	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system and as per technical data approved. 48" Sweep (1400mm) a.Regular model (23/23)	No	8.00		
47	Supply and fixinjg metal fan box with round hook	No	8.00		
48	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate.. Is 3854 and IS 1293. (16/3.7)	No	0.00		
	6Amps SP Switch (I No-3.7.1 of PWD S.R 2014-15)		5.00		
	6Amps 3way 5 pin socket (I No-3.7.3 of PWD S.R 2014-15)		2.00		
	32Amps Flush/projected types DP switch (I No-3.7.9 of PWD S.R 2014-15)		1.00		

No's of Corrections-0

49	Supplying and flush mounting powder coated metal / galvanised metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall (15/3.5)	Each	0.00		
	4-5Way (I No-3.5.2of PWD S.R 2014-15)		4.00		
	6Way (I No-3.5.3of PWD S.R 2014-15)		2.00		
	8Way (I No-3.5.4of PWD S.R 2014-15)		2.00		
	10-12Way (I No-3.5.5of PWD S.R 2014-15)		1.00		
50	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.(15/16/3.6)	Each	0.00		
	4Moudule (I No-3.6.2 of PWD S.R 2014-15)		4.00		
	6Moudule (I No-3.6.3 of PWD S.R 2014-15)		2.00		
	8Moudule (I No-3.6.4 of PWD S.R 2014-15)		2.00		

NO'S of correction - 0

	12Moudule (I No-3.6.6 of PWD S.R 2014-15)		1.00		
51	Supplying and fixing PVC/metal conduit accessories.(2/1.5)	Each	50.00		
52	~~KSRB 4-1.3~~ : Providing and laying in position plain cement concrete cum of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	23.40		
53	~~KSRB 4-1.6~~ ; Providing and laying in position plain cement concrete cum of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	23.40		
54	~~KSRRB 300-1~~. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete asper specifications. ~~MORTH/Chapter~~ 3	Cum	394.20		
55	~~KSRRB 300-1~~. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete asper specifications. ~~MORTH/Chapter~~ 3	Cum	239.40		
56	Removing B.S.Slabsand stacking etc complete.	Sqm	5280.00		

NO'S of Correction - Six (06)

57	Refixing stone slabs of drains and pointing in C.M (1:3).	Sqm	4224.00		
58	Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortor (1:6) including fixing curing etc,. Complete. 10cms thick	Sqm	1056.00		
59	~~KSRRB 200-8~~. Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of thorney jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications. ~~MORTH / Chapter~~ 2	Sqm	1760.00		
60	Earth work in soil with hydraulic excavator of 0.9 cu.m. bucket capacity including cutting and loading in tippers, trimming bottom and side slopes. In accordance with requirements of lines, grades and cross sections, and transporting to the embankment location and complete as per specifications.	Cum	662.55		
61	~~KSRRB M400-6.1~~. Construction of granular sub-base of Grading II Material by providing close graded material, mixing in a mechaical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. A. Plant Mix Method	Cum	331.28		
62	~~KSRRB 300-58~~. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. ~~MORTH~~ +	Sqm	2208.50		

No's of Correction - Five(05)

CONTRACTOR

EXECUTIVE ENGINEER

63	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap I basalt to wet mix macadam specifications including pre mixing the material with water at OMC mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406	Cum	441.70		
64	KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg I sqm using mechanical means complete as per specifications.MORTH Specification No. 502	Sqm	5210.00		
65	KSRRB 500-2. Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH specification clause 501	Sqm	9052.50		
66	KSRRB 500-7. Providing and applying tack coat using 80/100 grade bitumen(VGIO) on the prepared black topped surfaces at 2.5 kg per 10sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications.MORTH	Sqm	9052.50		
67	KSRRB M500-17. Providing and laying dense graded bituminous macadam using 100/120 TPH capacity H.M.P. with sensor paver Gr-li (50 mm to 75 mm) with 4.5 % VG-30 Bitumen grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications.	Cum	148.95		

No's of Correction - Nine (09)

CONTRACTOR

EXECUTIVE ENGINEER

68	KSRRB M500-19. Providing and laying bituminous concrete 40 mm thick with hot mix plant, using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 45 mm) with 5.4 % VG-30 Bitumen using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects complete as per specifications. ~~MORTH Specification~~	Cum	362.10		
69	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface - Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sq.m. area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC :35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications.	Sqm	622.50		

NO'S of Correction - Two (02)

Total NO'S of Correction - Sixty three (63)

DTS Approved